

Narrative of activity:

Construct a 12' x 20' deck in the rear of the house supported by sonotube piers. The construction will take place within the 100' Upland Review Area with less than 200 sq. ft. of area to be disturbed.

Erosion control measures will consist of a typical silt fence installation and hay bales between the activities and the swamp. Installation of those measures will take place prior to construction and will be maintained through out the duration of the project.

Excavated soils will be used to cover the area around the piers. Runoff from the deck will go through the joints in the deck flooring and onto a pea stone gravel base.